

RAC Tourism Assets Pty Ltd  
Monkey Mia Dolphin Resort  
Drainage Management Plan

6 July 2020

57540-129794 (Rev 2)

JBS&G Australia Pty Ltd T/A Strategen-JBS&G

## Table of Contents

1.	Summary.....	1
1.1	Corporate endorsement.....	1
2.	Context, scope and rationale.....	2
2.1	Scope .....	2
2.1.1	Key environmental factors.....	3
2.2	Requirements of MS 709.....	4
2.3	Rationale and approach in meeting the environmental objective .....	4
2.3.1	Rationale for choice of management targets .....	5
3.	Drainage management .....	6
3.1	Management actions.....	6
3.2	Management target .....	8
3.3	Monitoring.....	8
4.	Review and revision of management actions.....	9
4.1	Reporting provisions.....	9
4.1.1	Reporting on exceedance of the management target.....	9
5.	Adaptive management .....	11
6.	Stakeholder consultation.....	12
7.	Limitations .....	13
8.	References .....	14

## List of Tables

Table 1.1:	Environmental management targets .....	1
Table 2.1:	Key environmental factors, objectives and Project environmental aspects.....	3
Table 2.2:	Requirements of condition 7 of MS 709 .....	4
Table 3.1:	Risk-based management actions .....	7
Table 3.2:	Management targets.....	8
Table 3.3:	Monitoring program to achieve management targets .....	8
Table 4.1:	Corrective actions .....	9
Table 4.2:	Environmental management plan reporting table .....	10
Table 6.1:	Stakeholder consulted, comments and responses .....	12

## Appendices

Appendix A Overall masterplan

Appendix B Risk matrix

## 1. Summary

This Drainage Management Plan (DMP) is submitted in accordance with Ministerial Statement (MS) 709 Condition 7 for the Monkey Mia Dolphin Resort expansion (the Project) by RAC Tourism Assets Pty Ltd (RAC).

Table 1.1 below presents the environmental management targets to measure achievement of the conditioned environmental objective that must be met through implementation of this DMP.

**Table 1.1: Environmental management targets**

Required information	Response	
Title of proposal	Expansion of the Monkey Mia Dolphin Resort Monkey Mia, Shark Bay.	
Proponent	RAC Tourism Assets Pty Ltd.	
Ministerial Statement number	709.	
Purpose of this Condition EMP	The Drainage Management Plan is submitted to fulfil the requirements of Condition 7 of the above Statement.	
EPA's environmental objective for the key environmental factors	Environmental factor	EPA environmental objective
	Factor 4 Inland Waters	To maintain the hydrological regimes and quality of groundwater and surface water so that environmental values are protected.
	Factor 5 Marine Environmental Quality	To maintain the quality of water, sediment and biota so that the environmental values, both ecological and social, are protected.
Management targets	Environmental factor	Management targets
	Factor 4 Inland Waters	Prevent sediment from the Project area entering the ground and surface water environment (T4.1).
	Factor 5 Marine Environmental Quality	Prevent sediment from the Project area entering the marine environment. (T5.1) Prevent potential contaminants from the Project area entering the marine environment. (T5.2)

### 1.1 Corporate endorsement

I hereby certify that to the best of my knowledge, the Condition EMP provisions within this Drainage Management Plan are true and correct and address the legal requirements of condition 7 of Ministerial Statement No.709

[Signature of duly authorised proponent representative]

Name:

Signed:

Designation:

Date:

## 2. Context, scope and rationale

RAC Tourism Assets Pty Ltd (RAC) owns and manages the Monkey Mia Dolphin Resort (the proposal; Appendix A) located within a World Heritage area on a Shire of Shark Bay reserve. Approval for the proposal under the *Environmental Protection Act 1986* (EP Act) was granted to the former proponent Monkey Mia Dolphin Resort Pty Ltd through issue of MS 709 on 28 December 2005. A section 46 approval extending the period for substantial commencement was granted under MS 919 on 18 December 2012 to the then proponent, Aspen.

Substantial commencement of the proposal occurred in April 2013 with construction of the wastewater treatment plant, a key element of the proposal, which satisfied the requirement of condition 4 in MS 919.

Aspen transferred ownership to RAC in December 2015. An application to change conditions and increase the extent of the proposal in MS 709 under section 45C/46 of the EP Act, was submitted in April 2017.

In June 2017, the Deputy Chairman of the Environmental Protection Authority (under delegation authority from the Minister for Environment) approved changes to MS 709 under section 45C of the EP Act. The change to the proposal included:

- An increase in the clearing area for the wastewater treatment plan
- The development and use of borrow pits requiring 3.14 ha of vegetation clearing
- Administrative changes to Schedule 1 of MS 709 to describe the Development Envelope
- Simplification of the resort expansion and removal of elements to the design that were not relevant to the environment
- Schedule 1 of MS 709 was replaced by Attachment 1 and outlines the authorised extent of the physical and operational elements of the project (Appendix A).

Commencement of earthworks for the other key elements of the proposal, the resort expansion and staff accommodation facilities, commenced in October 2017 and were completed in October 2018.

MS 1067 was subsequently issued on 14 November 2017, changing conditions 3, 4 and 5 and deleting condition 6 of MS 709.

### 2.1 Scope

Condition 7 of MS 709 requires the proponent to prepare a DMP to ensure that stormwater runoff from the Project is being appropriately managed through the Project's drainage system during the operation phase (post construction phase) of the Project.

All actions associated with the management of drainage during construction are contained within the Construction Management Plan (CMP).

Given that the upgrading of the wastewater treatment plant was completed in 2014, this DMP specifically refers to the drainage management system associated with the resort expansion area and staff facilities area.

### 2.1.1 Key environmental factors

The environmental factors, EPA objectives and environmental aspects of the Project are provided in Table 2.1.

**Table 2.1: Key environmental factors, objectives and Project environmental aspects**

Factor	EPA objective	Environmental aspects of the Project
Factor 4 Inland Waters	To maintain the hydrological regimes and quality of groundwater and surface water so that environmental values are protected	Uncontrolled stormwater drainage has the potential to impact marine flora through smothering from sediment transport.
Factor 5 Marine Environmental Quality	To maintain the quality of water, sediment and biota so that the environmental values, both ecological and social, are protected.	

## 2.2 Requirements of MS 709

This DMP is submitted in accordance with condition 7 of MS 709. Table 2.2 details the requirements of this condition and also indicates which sections of this DMP they are addressed.

**Table 2.2: Requirements of condition 7 of MS 709**

Condition	Requirement	Section in DMP
7-1	Prior to commencement of construction associated with the resort expansion, the proponent shall prepare a Drainage Management Plan, to the requirements of the Minister for the Environment on advice of the Environmental Protection Authority. This Plan shall address:	DMP
	management of stormwater quality and quantity;	Section 3, Table 3.1, DMP 2; Section 3.3, Table 3.3, DMP M1.
	potential for erosion, local flooding and contaminant discharge;	Section 3, Table 3.1, DMP 1, DMP 2, DMP 5, and DMP M1; Section 3.3, DMP M1 and M2.
	minimising pollutants at their source; and	Section 3, Table 3.1, DMP 4; Section 3.3, Table 3.3, DMP M2.
	pollutant removal.	Section 3, Table 3.1, DMP 3 ; Section 4, Table 4.1, DMP CA2.
	Note: In preparation of advice to the Minister for the Environment, the Environmental Protection Authority expects that the advice of the following agencies will be obtained: Department of Conservation and Land Management; and Shire of Shark Bay.	Section 6
7-2	The proponent shall implement the Drainage Management Plan required by condition 7-1.	Section 2
7-3	The proponent shall make the Drainage Management Plan required by condition 7-1 publicly available.	Section 4.1

## 2.3 Rationale and approach in meeting the environmental objective

The approach for managing any potential drainage impacts is to develop a comprehensive management program that identifies:

- Management risks
- Key management based targets
- Management actions
- Monitoring measures
- Review and revision requirements.

An adaptive risk based management approach has been developed in order to create a robust management system, that prioritises and manages significant risks using the mitigation hierarchy (i.e. avoid, minimise, manage, rehabilitate and offset).

This management approach allows for flexibility, to enable the management program to adapt to any changes in the Project conditions, as well as to respond to the dynamic nature of the surrounding environment. The methodology for the risk-based approach is provided in Appendix A.

### **2.3.1 Rationale for choice of management targets**

Management targets (Table 3.2) were selected in order to prioritise the risks identified for the Project, and are based on a review of:

- Available data for the region
- The relationship between the project aspects and the environmental factors
- Industry standards and legislative requirements
- The requirements of MS 709.

### 3. Drainage management

The objective of the DMP is to identify the management provisions RAC proposes to implement to manage and minimise potential impacts from stormwater drainage during the operation phase of the Project in order to:

- Meet the EPA's objectives for inland waters and marine environmental quality as described in Table 2.1
- Meet the requirements of MS 709 (Table 2.2).

Stormwater management flows and dissipation rates have been considered in the planning and designs of the expansion resort area and staff accommodation facilities, including the camping areas.

The Construction Management Plan provides controls to ensure the potential impacts are contained by preventing stormwater egress during the construction phase.

Following construction, stormwater flows from roofs will be controlled through the stormwater containment system to prevent discharge to the foreshore/marine environment. Stormwater will be directed to and captured within any of four drainage/infiltration swales as identified within Appendix A.

In terms of meeting the requirements of Condition 7-1, the following areas have been identified:

- Areas of potential erosion:
  - Unsealed areas (such as grassed camping areas)
  - The foreshore reserve adjacent to the project area
- Areas of potential local flooding:
  - Impervious surfaces, including roads and access ways
  - Manhole and interceptor pits
- Areas of potential contaminant discharge:
  - Bunded fuel bowser
  - Chemical storage area.

#### 3.1 Management actions

Risk-based management actions have been identified and prioritised Table 3.1 based on the methodology provided in Appendix A. These management actions focus on Project operation activities that have the highest likelihood of causing environmental impact, and were specifically developed to reduce potential impacts of operation activities upon the surrounding marine environment.



**Table 3.1: Risk-based management actions**

Risk and key impacts	DMP management action reference	Management actions	Risk-based priority	Timing	Relevant management target	Status
Uncontrolled stormwater drainage has the potential to impact marine flora through smothering from sediment transport.	DMP 1	Maintain unsealed areas such as grassed camping areas and unsealed car parks to contain and infiltrate significant stormwater flows.	High	Operation	T4.1 and T5.1	Ongoing
	DMP 2	Direct stormwater flows from roofs, roads, access ways and other impervious surfaces to areas that are unsealed to enable infiltration close to source.	High	Operation	T4.1 and T5.1	Ongoing
	DMP 3	Maintain pollutant removal devices (i.e. oil, sediment and gross pollutant traps) to any outlet and overflow structure.	High	Operation	T5.2	Ongoing
	DMP 4	Ensure chemical and fuel storage areas are bunded.	High	At all times	T5.2	Ongoing
	DMP 5	'Cyclone Management Plan' to include protocols to reduce the stormwater impacts from cyclonic rainfall. Protocols will include inspections of the stormwater containment system and the site to prevent discharge to the foreshore/marine environment.	High	Operation	T4.1 and T5.1	Ongoing
	DMP 6	Remove sediment and debris from manholes/interceptor pits.	Medium	Operation	T4.1 and T5.1	Ongoing

### 3.2 Management target

Management targets have been developed to measure and report against the proposed RAC environmental objective (Table 3.2).

**Table 3.2: Management targets**

Environmental factor	EPA environmental objective	Management targets (Unique identifier)
Factor 4 Inland Waters	To maintain the hydrological regimes and quality of groundwater and surface water so that environmental values are protected.	Prevent sediment from the Project area entering the ground and surface water environment (T4.1).
Factor 5 Marine Environmental Quality	To maintain the quality of water, sediment and biota so that the environmental values, both ecological and social, are protected.	Prevent sediment from the Project area entering the marine environment. (T5.1) Prevent potential contaminants from the Project area entering the marine environment. (T5.2)

### 3.3 Monitoring

The purpose of monitoring program is to inform, through the management targets, if the environmental objective is being achieved, as well as to determine if management actions need to be reviewed and revised.

Table 3.3 outlines the monitoring program proposed to be undertaken by RAC.

**Table 3.3: Monitoring program to achieve management targets**

DMP monitoring action	Indicator	Parameter	Monitoring method	Frequency	Location	DMP management action reference	Relevant management target
DMP M1	Inspections of the stormwater system demonstrate that sediment and debris is not present.	Sediment	Visual assessment	Monthly, and following stormwater events	Storm-water system manholes/pits	DMP 3 DMP 6	T4.1 and T5.1
DMP M2	Inspections of chemical and fuel storage areas demonstrate that no spills/leaks have occurred.	Contaminants	Visual assessment	Weekly	Chemical and fuel storage areas	DMP 4	T5.2

## 4. Review and revision of management actions

In the event that management targets are not met, RAC will investigate the potential cause and any potential impacts that may have resulted. If the management targets are not met, and it is deemed to be the result of the project, the corrective actions detailed in Table 4.1 will be implemented.

**Table 4.1: Corrective actions**

DMP corrective action	Performance indicator	Action	Responsibility	DMP monitoring reference	Relevant management target
DMP CA1	Sediment and/or debris present in the stormwater system	Investigate cause and determine source. Remove sediment/debris. Continue monitoring. Revise and update risk assessment and management actions where applicable.	RAC	DMP M1	T4.1 and T5.1
DMP CA2	Spills and/or loss of containment has occurred at the chemical/fuel storage area	Investigate cause. Report spill to DPaW, DER and Shire of Shark Bay. Immediately cleanup and undertake remediation. Review procedures and undertake further training of staff. Continue monitoring. Revise and update risk assessment and management actions where applicable.	RAC	DMP M2	T5.2

### 4.1 Reporting provisions

The performance of the DMP will be assessed annually against the management targets in Table 3.2, and will be reported on as part of the Compliance Assessment Report (CAR). The DMP reporting template is presented in Table 4.2. This DMP is to be made publicly available in accordance with condition 7-3 of MS 709, via the RAC Parks and Resorts website.

#### 4.1.1 Reporting on exceedance of the management target

In the event that management targets are not met during the reporting period, a written report will be included in the CAR detailing the corrective actions that were undertaken, and the effectiveness of the corrective actions to rectify any potential impacts.

**Table 4.2: Environmental management plan reporting table**

Condition environmental objective and management target set in the Condition EMP		Reporting on the management objective and management target	Status <sup>1</sup>
EPA objective	Management target		
Factor 4 Inland Waters To maintain the hydrological regimes and quality of groundwater and surface water so that environmental values are protected.	Prevent sediment from the Project area entering the ground and surface water environment (T4.1).	Prevented sediment from the Project area entering the ground and surface water environment.	<ul style="list-style-type: none"> <li>● Yes</li> <li>● No</li> </ul>
Factor 5 Marine Environmental Quality To maintain the quality of water, sediment and biota so that the environmental values, both ecological and social, are protected.	Prevent sediment from the Project area entering the marine environment. (T5.1).	Prevented sediment from the Project area entering the marine environment.	<ul style="list-style-type: none"> <li>● Yes</li> <li>● No</li> </ul>
	Prevent potential contaminants from the Project area entering the marine environment. (T5.2)	Prevented potential contaminants from the Project area entering the marine environment.	<ul style="list-style-type: none"> <li>● Yes</li> <li>● No</li> </ul>

**Notes:**

<sup>1</sup>The status of achievement of the condition environmental objectives is indicated by the following symbols:

- Condition environmental objective achieved
- Condition environmental objective not achieved

## **5. Adaptive management**

RAC will implement an adaptive management system to provide a robust management plan, which effectively meets the environmental objectives. To achieve this, the DMP will be reviewed on an annual basis to ensure that the plan takes into consideration amendments to operations, monitoring results, audits, continuous improvement and changes in regulatory and corporate requirements. If revised, a copy of the revised DMP will be provided to Department of Water and Environmental Regulation as part of the CAR.

## 6. Stakeholder consultation

Consistent with the EPA's expectations for this DMP, RAC consulted with a number of stakeholders during the development of the plan.

This section provides a summary of consultation that occurred and key comments received from each stakeholder (Table 6.1).

**Table 6.1: Stakeholder consulted, comments and responses**

Organisation(s)	Comments	RAC response to comments/concerns
Department of Parks and Wildlife (previously known as Department of Conservation and Land Management CALM)	Nil	Nil.
Shire of Shark Bay (SoSB)	How will stormwater runoff from roofed areas be contained or redirected?	Stormwater flows from roofs will be controlled through the stormwater containment system to prevent discharge to the foreshore/marine environment. Stormwater will be re-used where possible as dust suppression and road watering during construction as outlined in Table 4 of the Construction Management Plan.
	How will groundwater runoff be redirected and any contaminants removed?	Hardstand runoff will be treated in water interceptors to remove oil and contaminants. Sediment traps will be installed to remove silt and withstand at least a 2 year ARI event as outlined in Table 4 of the Construction Management Plan.
	Provide details of type and details of stormwater storage areas (potential mosquito and midge breeding areas).	Stormwater storage areas will include storage ponds and dams where possible as outlined in Table 4 of the Construction Management Plan.
	Provide detailed stormwater management plan to be complied by a suitably qualified engineer that examines pre-development flows, proposed post development flows, soils, infiltration rates, the direction of proposed flows and if the camping areas will have the capacity to accommodate the stormwater runoff.	Stormwater management flows and dissipation rates have been considered in the planning and designs of the expansion resort area and staff accommodation facilities, including the camping areas. The 'Cyclone Management Plan' will be revised to include protocols to reduce the stormwater impacts from cyclonic rainfall. Protocols will include inspections of the stormwater containment system to prevent discharge to the foreshore/marine environment.

## **7. Limitations**

### **Scope of services**

This report ("the report") has been prepared by Strategen-JBS&G in accordance with the scope of services set out in the contract, or as otherwise agreed, between the Client and Strategen-JBS&G. In some circumstances, a range of factors such as time, budget, access and/or site disturbance constraints may have limited the scope of services. This report is strictly limited to the matters stated in it and is not to be read as extending, by implication, to any other matter in connection with the matters addressed in it.

### **Reliance on data**

In preparing the report, Strategen-JBS&G has relied upon data and other information provided by the Client and other individuals and organisations, most of which are referred to in the report ("the data"). Except as otherwise expressly stated in the report, Strategen-JBS&G has not verified the accuracy or completeness of the data. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations in the report ("conclusions") are based in whole or part on the data, those conclusions are contingent upon the accuracy and completeness of the data. Strategen-JBS&G has also not attempted to determine whether any material matter has been omitted from the data. Strategen-JBS&G will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to Strategen-JBS&G. The making of any assumption does not imply that Strategen-JBS&G has made any enquiry to verify the correctness of that assumption.

The report is based on conditions encountered and information received at the time of preparation of this report or the time that site investigations were carried out. Strategen-JBS&G disclaims responsibility for any changes that may have occurred after this time. This report and any legal issues arising from it are governed by and construed in accordance with the law of Western Australia as at the date of this report.

### **Environmental conclusions**

Within the limitations imposed by the scope of services, the preparation of this report has been undertaken and performed in a professional manner, in accordance with generally accepted environmental consulting practices. No other warranty, whether express or implied, is made.

The advice herein relates only to this project and all results conclusions and recommendations made should be reviewed by a competent person with experience in environmental investigations, before being used for any other purpose.

Strategen-JBS&G accepts no liability for use or interpretation by any person or body other than the client who commissioned the works. This report should not be reproduced without prior approval by the client, or amended in any way without prior approval by Strategen-JBS&G, and should not be relied upon by other parties, who should make their own enquiries.


## 8. References

RPS Bowman Bishaw Gorham (RPS) 2004, *Expansion of Monkey Mia Dolphin Resort Public Environmental Review (EPA Assessment Number 1455)*, report prepared for Monkey Mia Dolphin Resort Pty Ltd, Perth, June.



## Appendix A Overall masterplan





OVERALL MASTER PLAN  
SCALE 1:1000 @ A1, 1:500 @ A3

#### LEGEND

##### EXISTING BUILDINGS

BR BOUGHSHED RESTAURANT  
LV LIMESTONE VILLAS  
GV GARDEN VILLAS  
BV BEACH FRONT VILLAS  
DL DOLPHIN LODGE  
B1 - BEACHVIEW 1 BED  
SE - SHARED ENSUITE 2 BED  
D4 - 4 BED DORM  
D8 - 8 BED DORM  
DMA - DUTY MANGER'S ACCOMMODATION

##### BUILDINGS

K CAMP KITCHEN  
R RECREATION BUILDING  
C BBQ AND SEATING CABANA  
AM AMENITY AREA  
DC DRYING COURT  
FC FISH CLEANING STATION  
NC NEW CABINS  
2B 2 BED - NEW CABINS  
3B 3 BED - NEW CABINS  
UA 2B ACCESSIBLE 2 BED - NEW CABINS  
AR CABINS  
PAZ ARRIVALS BUILDING  
PE POOL AMENITY ZONE  
PN POOL EXISTING  
PG POOL NEW  
PLAY GROUND

SA1 STAFF ACCOMMODATION AREA  
SA2 STAFF ACCOMMODATION AREA  
MGR MANAGER'S ACCOM.  
AMGR ASSISTANT MANAGER'S ACCOM.  
HOD HEADS OF DEPARTMENT ACCOM.  
D DUPLEX (DOUBLES) STAFF ACCOM.  
SS SEASONAL STAFF ACCOM.  
RGV RELOCATED GARDEN VILLAS  
AVS ACCOMMODATION VEHICLE SITES  
AB RELOCATED EXISTING ABLUTION BLK  
SE SERVICES ENCLOSURE  
CS-01 CAMPING SITES (MIN SIZE 25m<sup>2</sup> NOMINAL 5x5m AND MINIMUM REGULATION SEPARATION SHOWN. SITES MAY BE LARGER OR AGGREGATED FOR LARGER GROUPS AT REDUCED YIELD) SITE SERVICES ZONE (LAUNDRY, WORKSHOP ETC)  
FB FUEL BOWSER  
FT FUEL TANK  
CD COACH DROP OFF  
DP DUMP POINT  
ST STORE RM  
RC RELOCATED CARAVANS (EXISTING)  
OF OFFICE  
SC SEWER PUMP STATION ENCLOSURE  
LD LAUNDRY  
GT GAS TANKS

SSZ  
FB  
FT  
CD  
DP  
ST  
RC  
OF  
SC  
LD  
GT

#### SYMBOL LEGEND

EXISTING BUILDINGS / INFRASTRUCTURE  
NEW BUILDINGS / REFURBISHED BUILDINGS  
PROPOSED DPAW LAND TO BE MODIFIED BUT NOT PART OF THIS DEVELOPMENT APPLICATION  
RELOCATION  
DEMOLITION  
ENSUITES  
GROUND WATER MONITORING WELL LOCATION  
MACERATOR PIT  
STAFF AREA  
EXISTING FENCE LINE  
LOCAL AUTHORITY DISCRETION REQUIRED FOR 90m RULE (CPCGR SCHEDULE 7: DIVISION 6. cl. 19.1 - ABLUTIONS AND TOILET FACILITIES, DIVISION 8 cl. 31 - WASHING UP FACILITIES FOR CAMPERS)

25m NOMINAL WIDE REDUCED FIRE LOAD ZONE  
NOMINAL 4m WIDE PROPOSED BATTER  
NOMINAL 5m CLEARED ZONE - IMMEDIATELY ADJACENT TO BOUNDARY  
NOMINAL 3m CLEARED ZONE  
NOMINAL 7m ZONE OF EXISTING VEGETATION TO BE MAINTAINED

#### STAFF ACCOMMODATION MODULES

3 ROOM FULL MODULE - HEADS OF DEPARTMENT  
2 ROOM DOUBLE MODULE - DOUBLE  
1 ROOM SINGLE MODULE - SEASONAL STAFF  
2 ROOM DOUBLE HALF MODULE - PERMANENT  
NEW CAR BAY PROVISIONS  
SA1 7 BAYS  
SA2 40 BAYS  
WORKSHOP 10 BAYS  
DOLPHIN LODGE, LIMESTONE VILLAS & CAMP SITES  
ADMIN & PARK ENTRY  
GARDEN VILLAS  
NEW BEACH CABINS  
126 BAYS (INCLUDES 37 OVERFLOW BAYS)  
1 TBA  
48 BAYS  
19 BAYS WITH BOAT LAYDOWN BESIDE

#### YIELD TABLE

GUEST ACCOMMODATION		
ACCOMMODATION VEHICLE SITES (ALL NEW)		
AVS	POWERED STANDARD	(105)
	POWERED STANDARD WITH ENSUITES	(14)
AVS	POWERED STANDARD ON BEACH FRONT	(10)
CAMPING SITES		
CS	NEW UNPOWERED CAMP SITES	81
BUILT ACCOMMODATION		
DL	EXISTING DOLPHIN LODGE	52
B1	BEACHVIEW 1 BED	(24)
SE	SHARED ENSUITE 2 BED PER ENSUITE	(16)
D8	DORMS 8 BED UNITS	(7)
D4	DORMS 4 BED UNITS	(5)
LV	EXISTING LIMESTONE VILLAS	14
BV	EXISTING BEACHFRONT VILLAS	8
GV	EXISTING DUPLEXED GARDEN VILLAS	30
RGV	RELOCATED DUPLEXED GARDEN VILLAS	8
NC	NEW CABINS ON BEACHFRONT - 2 BED (INCL. 1 ACCESSIBLE UNIT)	9
	NEW CABINS ON BEACHFRONT - 3 BED	3
GUEST ACCOMMODATION SUBTOTAL		334

STAFF & DPAW RESEARCH ACCOMMODATION (ALL NEW U.O.N)		
SA1A	STAFF ACCOMMODATION	22
	MGR MGR'S RESIDENCE	(1)
	AMGR ASST. MGR'S RESIDENCE	(1)
	HD HEADS OF DEPARTMENT - (FULL MODULE)	(2)
	RC RELOCATED CARAVANS - (EXISTING)	(6)
	SS SEASONAL STAFF - (QUARTER MODULE)	(12)
SA1A	OFFICE	2
	OF OFFICE - (HALF MODULE - 2 ROOM)	(2)
SA2A	STAFF ACCOMMODATION	56
	HD HEADS OF DEPARTMENT - (FULL MODULE)	(4)
	PS PERMANENT STAFF - (HALF MODULE)	(28)
	SS SEASONAL STAFF - (QUARTER MODULE)	(24)
DMA	EXISTING DUTY MANGER'S RESIDENCE (DOLPHIN LODGE)	1
STAFF & DPAW RESEARCH ACCOMMODATION SUBTOTAL		81
* ALLOCATION OF ACCOMMODATION IS INDICATIVE ONLY		

GUEST & STAFF ACCOMMODATION TOTAL ON COMPLETION 415

- Point of entry to beach
- Fencing
- Drainage Tank / Infiltration Swale
- Chemical Storage Area
- Bunded Fuel Bowser
- Grease Trap/Tank
- Grassed Area
- Sealed/ Paved Area
- Shell Grit
- Pindan

Rev	Date	Issued To
12	21.08.18	ISSUED TO CONSULTS, CLIENT & BLD
11	10.07.18	ISSUED TO CONTRACTOR & SURVEYOR & LANDSCAPE
10	15.06.18	ISSUED TO CLIENT & BLD
9	25.05.18	ISSUED TO CONSULTS & BLD
9	21.05.18	ISSUED TO CONSULTS & BLD
8	16.05.18	ISSUED TO CONSULTS & BLD
7	20.04.18	ISSUED TO CONSULTS & BLD
6	16.03.18	ISSUED TO BPA, DG Cons.
5	14.02.18	ISSUED TO DDM
4	11.12.17	ISSUED TO BPA, AMS, BESEEN & BLACKWELL
3	04.12.17	ISSUED TO BPA AND AMS
2	01.12.17	ISSUED TO STRATEGEN
1	23.11.17	ISSUED TO DDM

Rev	Date	Description
12	21.08.18	AERIAL PHOTO UPDATE (19.08.18)
11	10.07.18	DBCA & ARRIVALS BACKGROUNDS UPDATED
10	15.06.18	SITE MARKERS ADDED, STREET NAMES UPDATED
9	25.05.18	AERIAL PHOTO UPDATED (19.05.18)
9	21.05.18	ENTRY ROAD ADJUSTED, DB07 REPOSITIONED, 1ST AVE RE-ALIGNED, COORDS PROVIDED
8	16.05.18	ENTRY POINT & MAIN ST ROAD RE-ALIGNMENT, C/PARK LAYOUT CHANGED TO SUIT EXIST TREES
7	20.04.18	AERIAL PHOTO UPDATED, 3 BED UNIT REPOSITIONED, WADING POOL REPOSITIONED
6	16.03.18	MODIFIED FUEL TANK POSITION
5	14.02.18	SWAP CABANA WITH AVS-E SITE IN AVS-04. POOL FOOT PRINT CHANGED
4	08.12.17	INSERT PAZ FOOTPRINT
3	04.12.17	INSERT SA2 LAUNDRY AND STAFF QUARTERS SHIFTED TO SUIT 3m CLEARANCE
2	01.12.17	INSERT BUSHFIRE CLEARANCE ZONES
1	23.11.17	INITIAL ISSUE

## CONTRACT DOCS

Job Title  
**MMDR**  
MONKEY MIA DOLPHIN RESORT

Sheet Title  
**OVERALL MASTERPLAN**

Scale 1:1000  
Job No. 16-131

Drawn PGA Checked PGA Date AUG 2017

PERTH  
Level 1 | 19 Havelock Street | West Perth | WA 6005  
t 08 9485 2122  
f 08 9485 2037  
e admin@patergroup.com.au  
w www.patergroup.com.au

CLIENT:  
**RAC**  
**Monkey Mia Dolphin Resort**  
For the better



## Appendix B Risk matrix

### Risk-based priority

A risk assessment determines whether a hazard could harm the environment. The following stages are undertaken once an environmental hazard has been identified

- Stage 1: Risk identification to identify and document environmental risks and impacts associated with the organisation activities, goods and services
- Stage 2: Qualitatively ranking potential environmental impacts to establish relative significance
- Stage 3: Establishing and documenting control measures to mitigate potentially significant environmental impacts.

RAC shall control all environmental risks identified within the organisation to an extent that is practically possible (Table A 1), once they have been identified through the risk management and identification process.

Risk ranking is generally undertaken by assigning likelihood and consequence levels to each identified activity or issue and determining risk levels through the use of a risk matrix. After completing this process management measures are implemented and a residual risk is determined.

**Table A 1: Qualitative risk rating matrix**

	Consequences			
Likelihood	Critical (4)	Major (3)	Moderate (2)	Minor (1)
Almost Certain (A)	VH	VH	H	M
Likely (B)	VH	VH	H	M
Unlikely (C)	VH	H	M	L
Rare (D)	H	M	L	L

VH	Very High	Immediate action required. Task stopped.
H	High	Senior Management attention needed.
M	Medium	Management responsibility must be specified.
L	Low	Manage by routine procedures.

**Table A 2: Likelihood Classification**

Likelihood	Description
Almost Certain (A)	Event is a common or frequent occurrence and is expected to occur daily
Likely (B)	Event is expected to occur annually.
Unlikely (C)	Event may occur. If the event has occurrence in the project area it is very infrequent. It is likely to have occurred within the industry.
Rare (D)	The event is unlikely to not occur in the project area but has been known to occur infrequently within the industry. The event may occur at a frequency of more than 10 years.

**Table A 3: Consequence Classification**

Consequence	Definition
Critical (4)	<b>Environment:</b> Long term large scale damage to habitat or environment. <b>Legal:</b> Non-compliance having a critical financial or community profile impact. <b>Community:</b> Widespread community disruption with significant adverse economic impact.
Major (3)	<b>Environment:</b> Severe impact requiring remedial damage to environment. <b>Legal:</b> Non-compliance and having high financial or community profile impact. <b>Community:</b> Extensive community complaints extending beyond the region or adverse state level media coverage. Wider community disruption up to 7 days with adverse economic impact.
Moderate (2)	<b>Safety:</b> Moderate impact on environment. No long term or irreversible damage. <b>Legal:</b> Non-compliance having moderate financial or community profile impact. <b>Community:</b> Widespread local complaints or adverse regional media coverage. Isolated community disruption up to 3 days with limited adverse economic impact.
Minor (1)	<b>Environment:</b> Minor breach of environmental policy. Negligible impact on environment. <b>Legal:</b> Technical breach with no sanction. <b>Community:</b> Few complaints or minor adverse media coverage. Negligible impact on reputation. Isolated community disruption up to 1 day with minimal economic.

When determining risk controls, the hierarchy of risk controls, summarised in Table A 4 must be considered.

**Table A 4: Hierarchy of risk controls**

Option	Examples
Elimination	Stop using equipment or substance, or stop undertaking the procedure causing the risk.
Substitution	Use an alternative substance, equipment or process which poses less risk.
Isolation	Separate receivers from the source of the risk.
Engineering Controls	Reduce exposure to the risk by making physical changes to equipment, procedures or the work environment (e.g. using dust control measures on equipment).
Change work practices	Adopt work procedures which minimise exposure to the risk (e.g. wet sweeping a dusty environment rather than dry sweeping, to minimise the amount of airborne dust).


© JBS&G Australia Pty Ltd T/A Strategen-JBS&G

This document is and shall remain the property of Strategen-JBS&G. The document may only be used for the purposes for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

#### Document Distribution

Rev No.	Copies	Recipient	Date
2	1 (Electronic	DWER	06 July 2020

#### Document Status

Rev No.	Author	Reviewer	Approved for Issue		
		Name	Name	Signature	Date
A	D. White, B. Downe / A. Welker, D. Goundrey				29 April 2016
0	B. Downe, A. Welker / D. Goundrey				24 June 2016
B2	T. George / M. Brook				3 April 2017
1	T. George / M. Brook				11 April 2017
2	W. Oversby	K.Moyle	K. Moyle		06 July 2020

